Construction of a block of Operators' Quarters, to accommodate two families at Chikballapur.

No.	Items of work	Unit	Quantity	Rate Rs. a. p.
1	Earthwork excavation and filling in basement	C.yd.	51	
2a	Stone jelly in chunam mortar concrete foundations ...	C.ft.	583	
b	Stone in clay, foundation and basement ...	„	1,055	
c	Burnt brick in clay, superstucture	„	3,058	
d	Stone slabs 5" thick roughly dressed and set in mortar	„	217	
e	Do 4" thick roughly dressed and set in mortar.	„	24	
f	Chunam plastering two coats	Sqr.	61.87	
g	Chunam pointing	„	2·10	
h	Binding wall 1—1/8' x 9" brick in clay and chunam plastering.	R.ft.	50	
i	Plain cornice, 6" projection	„	50	
j	Constructing sinks complete	Each	5	
k	Providing mortar and pestle	„	2	
3	Flooring with 3" lime concrete and chunam plastering with a floating coat of cement.	Sqr.	8.79	
4a	Roofing with 1st Class Mangalore tiles on teak reepers 2" x 1" complete.	„	11·24	
b	Ridge tiles set in mortar and cement pointed ...	R.ft.	41	
c	Cuddapah slab terrace with cudapah slaps 1½" thick, 3" concrete and plastering on top complete.	Sqr.	3·20	
d	Burnt brick in mortar 9" projection ...	R.ft.	63	
e	Burnt brick in mortar parapet wall 1½' high as per plan.	„	59	
5a	Matty wood work wrought and put up with two coats of wood oiling.	C.ft.	35·28	
b	Doors with teak frames and honney wood battened shutters 1" thick with iron fixtures.	S.ft.	240·50	
c	Window with teakwood frames and honney wood battened shutters 1" thick and iron bars 5/8" diameter complete.	„	96	
d	Honney wood planks 1" thick for shelves fixed on teakwood pegs complete.	„	48	
e	Chacolate painting two coats	Sqr.	12·18	
f	Expanded metal 3" x 1½" x 1/8" mesh fixed on teakwood frames complete.	S.ft.	75	
6a	Rolled steel girders fixed complete (continental) ..	Cwt.	18·45	
b	Rain water down pipes 3' diameter fixed complete ...	R.ft.	20	

C. M. CARIAPA,
Chief Electrical Engineer.

KOLAR DIVISION.

Notice dated 26th September 1930.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, Part VI, page 1170, dated 25th September 1930, calling for tenders for widening and revetting the well in the Government Silk Farm at Kolar Taluk.

The latest date for tender is 18th October 1930.

Notice.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, Part VI, pages 1168 to 1169, dated 25th September 1930, calling for tenders for restoring Siddaghatta tank, Mulbagal Taluk.

The latest date for tender is 18th October 1930.

N. LAKSHMINARASIMHAIA,
Executive Engineer.